

THESE TEXTS ARE USED EXCLUSIVELY FOR ADVISORY PURPOSES.

DEPENDING ON THE PROGRESS OF THE WORK AND WITHOUT ANY EXTERNAL HELP, THE SOFTWARE DISPLAYS THE FOLLOWING REPORTS BY DEFAULT:

- 1) DETAILED STEPS
- 2) DETAILED PRODUCTS
- 3) COMPILED PRODUCTS
- 4) FINANCIAL INSTITUTIONS
- 5) PURCHASE ORDERS

AS AN EXAMPLE, THE SOFTWARE DISPLAYS THE FOLLOWING REPORT (3) CONCERNING THE COMPILED PRODUCTS OF THE PROJECT:

## Products Compiled

<u>Various</u>	<u>919.00 \$</u>
<u>Digging</u>	<u>6,025.00 \$</u>
<u>Land Surveyor</u>	<u>2,475.00 \$</u>
<u>Embankment (Material &amp; Transport)</u>	<u>1,342.00 \$</u>
<u>Concrete's Footing (Material)</u>	<u>2,880.00 \$</u>
<u>Concrete's Wall (Material)</u>	<u>5,520.00 \$</u>
<u>Concrete's Floor (Material)</u>	<u>2,640.00 \$</u>
<u>Concrete's Balcony (Material)</u>	<u>240.00 \$</u>
<u>Rebar (Material)</u>	<u>952.97 \$</u>
<u>Concrete's Pump</u>	<u>2,050.00 \$</u>
<u>Waterproofing</u>	<u>430.00 \$</u>
<u>Formwork</u>	<u>5,685.20 \$</u>
<u>Foundation's Material</u>	<u>1,426.82 \$</u>
<u>Carpentry (Install)</u>	<u>19,821.25 \$</u>
<u>Cement's Worker</u>	<u>907.00 \$</u>
<u>Trust &amp; Joist (Material)</u>	<u>15,945.00 \$</u>
<u>Basement's Wall (Material)</u>	<u>5.99 \$</u>
<u>First's Floor (Material)</u>	<u>1,349.91 \$</u>
<u>First's Wall (Material)</u>	<u>2,498.10 \$</u>
<u>Wooden Balcony (Material)</u>	<u>481.05 \$</u>
<u>Garage's Wall (Material)</u>	<u>1,346.99 \$</u>
<u>Second's Floor (Material)</u>	<u>1,205.10 \$</u>
<u>Second's Wall (Material)</u>	<u>2,670.02 \$</u>

<b>Floor</b>	<b>Building</b>	<b>Quantity</b>	<b>Product</b>
Second floor	Structure	29 Unit	Panel Tentest Black 4 'x 9'

<b>Floor</b>	<b>Building</b>	<b>Quantity</b>	<b>Product</b>
Second floor	Structure	2 Unit	Rlx Vapor Barrier (Novawrap) 10'x
Second floor	Structure	2 Unit	Foam 4 " X 100 '
Second floor	Structure	33 LinearUnit	Stud 2 X 6 X 16
Second floor	Structure	5 LinearUnit	Joist 2 X 10 X 14
Second floor	Structure	72 LinearUnit	Board 1 X 4 X 10
Second floor	Structure	1 LinearUnit	Roll Polyethylene Nevrastral 12 "
Second floor	Structure	9 LinearUnit	Stud 2 X 4 X 12
Second floor	Structure	113 LinearUnit	Stud 2 X 6 X 93 1/4

[Roof \(Material\) 6,921.32 \\$](#)

[Roofer \(Install & Material\) 2,975.00 \\$](#)

[Sash & Door \(Material\) 8,670.00 \\$](#)

[Insurance 1,500.00 \\$](#)

[Garage's Door \(Install & Material\) 1,350.00 \\$](#)

[Partition \(Material\) 3,129.39 \\$](#)

[Insulation \(Material\) 1,936.08 \\$](#)

<b>Floor</b>	<b>Building</b>	<b>Quantity</b>	<b>Product</b>
Foundation	Structure	1 Unit	Polythene 10'x 100' 10mil.
Basement	Structure	1 Unit	Polythene 20'X100' 6mil.
First floor	Structure	1 Unit	Polythene 20'X100' 6mil.
First floor	Structure	11 Unit	Wool (Wood) R20/15 ( 78.3 ' )
First floor	Structure	2 Unit	Polythene 10'x 100' 10mil.
Second floor	Structure	1 Unit	Polythene 20'X100' 6mil.
Second floor	Structure	11 Unit	Wool (Wood) R20/15 ( 78.3 ' )

<b>Floor</b>	<b>Building</b>	<b>Quantity</b>	<b>Product</b>
Second floor	Structure	2 Unit	Polythene 10'x 100' 10mil.
Garage	Structure	1 Unit	Polythene 20'X100' 6mil.
Garage	Structure	4 Unit	Wool (Wood) R20/15 ( 78.3 ' )
Garage	Structure	1 Unit	Polythene 10'x 100' 10mil.
Garage	Structure	7 SurfaceUnit	Insulating 2 " Type 4 (R-10)

[Blown wool \(Install & Material\) 908.00 \\$](#)

[Urethane \(Install & Material\) 1,905.00 \\$](#)

[Plumbing \(Install & Material\) 7,323.00 \\$](#)

[Electricity \(Install & Material\) 11,300.00 \\$](#)

[Ventilation/Heating \(Install & Material\) 3,100.00 \\$](#)

[Gypsum \(Material\) 3,363.00 \\$](#)

<b>Floor</b>	<b>Building</b>	<b>Quantity</b>	<b>Product</b>
Foundation	Structure	14 SurfaceUnit	Regular 1/2X4X12
Basement	Maison	8 SurfaceUnit	Regular 1/2X4X12
First floor	Maison	56 SurfaceUnit	Regular 1/2X4X12
Second floor	Maison	61 SurfaceUnit	Regular 1/2X4X12
Second floor	Maison	16 SurfaceUnit	Waterproof 1/2x4x8
Garage	Maison	17 Unit	Fireproof 1/2" x4'x12'

Drywall 12,099.20 \$  
Woodwork (Material) 2,205.14 \$  
Carpentry trim (Install) 2,849.00 \$  
Stair (Material) 2,440.00 \$  
Stair (Install) 1,643.00 \$  
Bricks & Stone (Material) 3,586.00 \$  
Paint (Install & Material) 5,900.00 \$  
Brick & Stone (Install) 8,088.10 \$  
Iron's Angle (Material) 324.55 \$  
Wall's Lining (Install & Material) 12,940.00 \$  
Plaster & Acrylic 261.00 \$  
Floor Covering (Install & Material) 7,666.00 \$  
Ceramic (Install & Material) 2,977.00 \$  
Cupboard (Material & Lay) 9,925.00 \$

**Subtotal: 206,101.18 \$**  
**Provincial taxes (9.975 %): 20,558.593 \$**  
**Federal taxes (5.000 %): 10,305.059 \$**  
**Total: 236,964.83 \$**